



1

FOOD CORPORATION OF INDIA

ISO 9001 - 2000 CERTIFIED

ENGINEERING DIVISION

REGIONAL OFFICE

124, GREAMS ROAD, CHENNAI - 600 006.

PRICE BLD

TENDER DOCUMENT

VOL. II

SCHEDULE OF QUANTITIES

Name of Work: Construction of Regional Office / District Office building along with commercial space at FSD, Egmore complex, Cheet pet, ch-31. SH. - Providing 2 nos of tube wells. (recall)

Contractor

80

Asst. Genl. Manager (CE/Estt)


FOOD CORPORATION OF INDIA

SCHEDULE OF QUANTITIES

Name of Work : Construction of multi storied Regional Office / District Office building with ancillaries and services including internal / external electrification, public address system and firm alarms at FCI, FSD, Egmore complex, cheppei, Chennai -31. SH: Providing 2 Nos of tube well. (Recall)

Item No.	Item of Work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
MARKET RATE ITEMS						
25.44	Drilling 300mm dia borewell upto hard rock formation in alluvial soil sedimentary strata of clay, sand stone, shale pebbles etc., by first taking a pilot bore of 150mm dia and enlarging to 300mm dia by direct or reverse rotary mud circulation method using contractors rig, fuel, labour and bentonite mud at the site shown by the Engineer-in-charge including construction of mud pit etc., complete in two places.	42.0000 Mts	Mts			
25.45	Supplying and lowering 180mm dia PVC pipe of approved brand and manufacture with / without slot of threaded S & S pipe including the cost of cutting, threading, coupling making slots and labour for erection etc., complete.	44.0000 Mts	Mts			
25.46	Supplying and packing the gap between the soil surface and casing pipe outface with pebbles of suitable size.	2.0000 Cum	Cum			
25.47	Drilling 165mm dia holes in hard rock / boulders to any required depth below alluvial / sedimentary formation as directed by the Engineer-in-charge using contractor power rig, fuel, labour etc., complete	78.0000 Mts	Mts			
25.48	Supplying and lowering 140mm dia PVC pipe of approved brand and manufacture with slots and with / without thread for required depth including the cost of cutting, threading, coupling etc., complete.	78.0000 Mts	Mts			

Contractor


Assistant General Manager (C.E.)


(2)

Item No.	Item of Work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
25.49	Developing the borewell with Air compressor of required capacity including transportation, labour and fuel charges for compressor as directed by the Engineer-in-charge.	8.0000	1 hr			

(Rupees

Only)

Contractor


Assistant General Manager (Civil)