

FOOD CORPORATION OF INDIA
ENGG. DIVISION: INDUSTRIAL ESTATE, PALAKKAD 678731.
ISO 9001:2008 CERTIFIED

1 of 3

TENDER SCHEDULE

Name of Work: Extension for the labour rest shed at FSD Nilswaram

Sl.No	Approximate Quantity	Description	Unit	Rate in (Figures/Words)Rs.	Amount
1	3.50	Earth works in excavation by mechanical means (hydraulic excavators)/manual means in foundation trenches or drains not exceeding 1.50m in width or 10 sqm. On plan including dressing of sides and ramming of bottoms lift up to 1.50m including getting out the excavated soil and disposal of surplus excavated soil as directed with in a lead of 50 m in all classes of soil Ref. DSR.2007.2.8.1 in all kind of soil	Cum	103.4 (Rupees one hundred three and forty)	361.90
2	3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all work up to plinth level with CC 15.10 (1 cement 5 coarse sand 10 graded coarse aggregate 40 mm nominal size) Ref. DSR 2007-4.110	Cum	2237.75 (Rupees two thousand two hundred thirty seven and paise seventy five)	6713.25
3	3.60	Neatly dressed laterite stone masonry in cement mortar 1:5 (1 cement 5 coarse sand) for foundation and plinth)	Cum	2567.79 (Rupees two thousand five hundred sixty seven and paise seventy nine only)	9244.04
4	6.40	Neatly dressed laterite stone masonry in cement mortar 1:5 cement. 5 coarse sand) for super structure	Cum	2753.63 (Rupees Two Thousand Seven Hundred and Fifty Three and Paise Sixty Three only)	17623.23
5	3.50	Filling available excavate earth (excluding rock) in trenches, plinth sides of foundation etc. in layers not exceeding 20 cms. In depth consolidating each deposited layer by ramming and watering lead up to 50m	Cum	45.70 (Rupees Forty Five and Paise Seventy only)	159.95
6	189.00	Supplying and fixing M.S. Pipe of required dia including cutting welding making anchor plate where ever necessary etc. complete as directed.	Cum	61.50 (Rupees Sixty One and Paise Fifty only)	10393.50
7	0.45	Reinforced cement concrete work in beams, suspended floor, floors, landings balconies, shelves, chajass, lintels, beams, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centring shuttering finishing and reinforcement with 1:2:4 (1 cement 2 coarse sand 4 graded stone aggregate 20 mm nominal size)	Cum	3673.85 (Rupees Three Thousand Six Hundred and eighty Three and Paise Eighty Five only)	1653.23
8	0.40	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, plain window sills, fillets, etc., upto 5 floor levels excluding the cost of centring, shuttering and finishing.	Cum	3579.10 (Rupees Three Thousand Five Hundred and Seventy Nine and Paise Ten only)	1431.64

9	13.00	Centring and shuttering including strutting, propping etc. and removed of form of lintels beams, plinth beams, girders, bressumers and cantilevers	Sqm	162.65 (Rupees One Hundred and Sixty Two and Paise Sixty Five only)	2114.45
10	3.20	Centring and shuttering including strutting, propping etc. and removed of form of small lintels not exceeding 1.50m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed clocks and the like	Sqm	119.25 (Rupees One Hundred and Nineteen and Paise Twenty Five only)	381.60
11	50.00	Reinforcement of RCC work including straightening cutting bending and placing in position and binding all complete - Cold twisted bars	Kg	42.70 (Rupees Forty Two and Paise Seventy only)	2135.00
12	29.00	Providing asbestos cement (6mm thick corrugated sheet roofing with fixing GI J or L hooks bolts and nuts 8mm dia GI plain and bitumen washers complete excluding the cost of purlins, rafters and trusses. Corugated sheets upto 60 degrees pitch	Sqm	240.72 (Rupees Two Hudred and Forty and Paise Seventy Two only)	6980.92
13	4.00	Providing and fixing ridges and hips in asbestos cement sheet roofing Close fitting adjustable ridges	m	235.91 (Two Hundred and Thirty Five and Ninety One only)	943.62
14	19.00	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of teps etc complete 40mm thick with 20mm nominal size stone aggregate)	Sqm	192.95 (Rupees One Hundred and Ninety Two and Paise Ninety Five only)	3666.05
15	42.00	Plastering with cement plaster of mix 1:4 (1 cement: 4 fine sand) 12mm thick	Sqm	77.55 (Rupees Seventy Seven and Paise Fifty Five only)	3257.10
16	29.00	Plastering with cement plaster of mix 1:4 (1 cement: 4 fine sand) 15mm thick	Sqm	90.35 (Rupees Ninety and Paise Thirty Five only)	2620.15
17	42.00	White washing with lime to give an even shade on new work	Sqm	6.75 (Rupees Six and Paise Seventy Five only)	283.50
18	29.00	Finishing walls with water proof cement paint "Snow cem plus" of M/s.Snowcem India Ltd., or equivalent of required shade New work Two or more coats applied at 3.84Kg/10 Sqm.	Sqm	30.80 (Rupees Thirty and Paise Eighty only)	893.20
19	7.00	Painting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade Two or more coats on new work over and under a coat of suitable shade with ordinary paint of approved brand and manufacture	Sqm	51.30 (Rupees Fifty One and Paise thirty only)	359.10
20	4.00	Extra labour for dismantling the existing AC sheet over the roof of rest room and fixing the same.	Each	155.54 (Rupees One Hundred and Fifty Five and Paise Fifty Four only)	622.16
21	6.00	Supplying and filling earth obtained from approved source (excluding rock) in layers and exceeding 20cm in depth breaking clods, watering, rolling each layer by using power road roller of 8 tonnes capacity and dressing up in embankments for roads, plinth fillings or filing up ground depression inclusive of royalty, seigniorage, etc.	Cum	237.38 (Two Hundred and Thirty Seven and Paise Thirty Eight only)	1424.28
		Total			73261.87

